

15-135-20079-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

NOV 13 1967
11-13-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name McKnab Production Company

Complete Address: Midlands Savings Bldg., Denver, Colorado

Lease Name Irvine Well No. 1

Location SW/4 NW/4 Sec. 1 Twp. 17 Rge. 21 (E) (W) X

County Ness Total Depth 4140

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Omega Drilling, Inc.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 12:30 A Day 10 Month 11 Year 1967

The Above well was plugged as follows:

RTD 4140' 8 5/8 csg set at 386' cwc
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 390' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/14/67
INV. NO. 6671-W