

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-051-19437-00-00

FILE NO. 25-15

LOCATION NE NE SW

SEC. 32 TWP. 13 RGE. 16

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Kuhn

Operator Shamrock Drg Co Address ^{Box 793} Oklahoma City

Field _____ County Ellis

Total Depth 3427 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 150' circulated with cement.

5 1/2" at 3425' with 75 sax cement behind.

Sand to 3420', set 4 sax cement with dump bailer, pulled

2635' 5 1/2", filled with mud to 150', set rock and 15 sax cement,

mud to 55', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1952

CONSERVATION DIVISION
Wichita, Kansas
District Conservation Agent

Date 6-24-52