

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

AUG 25 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. A. Allison 15-051-20839-00-00

Complete Address 1415 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name C. P. Braun Well No. 1

Location SW NE SW Sec. 32 Twp. 13 Rge. (E) (W) 16

County Ellis Total Depth 3472'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1 P Day 22 Month 8 Year 1972

The above well was plugged as follows:

RTD 3472' 8 5/8 csg set at 215' cwc: Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 250' set cementing plug and displaced 25 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 8/25/72
INV. NO. 6231-W