

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,874-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Energy Three, Inc.

Complete Address P.O. Box 1505, Great Bend, Ks. 67530

Lease Name E. Dinkel Well No. 1

Location 80' N. & 60' E. of SW SW Sec. 32 Twp. 13 Rge. 16 (East) (West)

County Ellis Total Depth 3500'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Big Three Drilling, Inc.

Address P.O. Box 52, Gorham, Ks. 67640 License No.

Operation Completed: Hour: 7:45 PM Day: 14 Month: March Year: 19 82

Plugging Operations attended by Agent?: All XXX Part None

The above well was plugged as follows:

8 5/8"-263' S.P. cuc. w/165 sacks common-2% Gel.-3% Cal.Cl.

Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement

Circulate 10 sacks in rat hole and 5 sacks in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1982

CONSERVATION DIVISION
WICHITA, KANSAS

Amount of Surface Casing: 263' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:
Conservation Division Agent

INVOICED

DATE 3-26-82

INV. NO. 9742-W

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

March 26, 1982

INVOICE NUMBER: 9742-W

TO: Energy Three Inc.
Box 1505
Great Bend Kansas 67530

15-051-22874-00-00

PLUGGING ASSESSMENT AS FOLLOWS:

PAYABLE UPON RECEIPT

E. Dinkel #1
80'N & 60'E of SW SW Sec.32-13-16W
Ellis
3500' \$113.75

NOTE: We also need the following before our file is completed:


- X _____ Well Plugging Record (CP-4)
- X _____ Well Log
- X _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



Administrator

Mr. Gilbert Scheck 2202 Canterbury Rd., Hays Ks. 67601 (913) 628-2600

is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE