

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1963

Operator's Full Name Kansas Natural Gas Inc. CONSERVATION DIVISION
Wichita, Kansas

Complete Address: Box 599 Hays, Kansas

Lease Name Frost Well No. 1

Location Center Sec. 5 Twp. 25 Rge. 35 (E) (W)

County Kearny Total Depth 2652'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sun Cementing Company

Address: Liberal, Kansas License No.

Operation Completed: Hour 3 PM Day 11 Month 10 Year 63

The Above well was plugged as follows:

10 3/4"-600' Circulated w/cement. 7" - 2415' Circulated w/cement.

5" Linner Perforated, 238' Circulated w/cement.

2 Sax.Hulls, 6 Sax.mud, 250 Sax.cement 2652' to 1402'

Mud 1402' to 1250' 250 Sax.cement 1250' to surface.

Weld plate on surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/14/63

INV. NO. 9890-W