

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22372-00-00
Spot: CSWSWNW Sec/Twnshp/Rge: 26-13S-20W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: YOUNGER B Well Number: 6
County: ELLIS Total Vertical Depth: 3855 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 166 w/150 sxs cmt
Production: Size 5.5 feet: 3849 w/150 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/07/2001 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Revd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed Plugging Method: Ordered 295 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/07/2001 10:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs at 750' - 1500' - 2240'.
8 5/8" S.P. at 166' w/150 sxs cmt. 5 1/2" casing at 3849' w/150 sxs.
Tubing to 2010' - pumped 100 sxs cement and 500# hulls.
Pulled tubing to 1000' - pumped 85 sxs cement to circulate.
Pulled all tubing and topped off with 45 sxs cement.
8 5/8" S.P. to Max. P.S.I. 500#. Held.
Total of 230 sxs 60/40 pozmix - 10% gel and 500# hulls.

Remarks: SWIFT SERVICES, INC. - WERTH TANK - WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

RECEIVED

NOV 26 2001

KCC WICHITA

NOV 15 2001

