

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22142-00-00  
Spot: CSWNWNW Sec/Twnshp/Rge: 26-13S-20W  
4290 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: YOUNGER B Well Number: 2  
County: ELLIS Total Vertical Depth: 3845 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 168 w/135 sxs cmt  
Production: Size 5.5 feet: 3842 w/150 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/06/2001 10:30 AM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: DUANCE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed  
Plugging  
Method:

Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/06/2001 11:15 AM

KCC Agent: JAY PFEIFER

Actual Plugging Report:


Perforated casing at 775' - 1525' - 2265'.  
Tied onto 5 1/2" and pumped to pressure with 245 sxs and 500# hulls.  
Max. P.S.I. 400#. S.I.P. 50#.  
Hooked onto annulus and pumped 5 sxs. Max. P.S.I. 500#.

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

RECEIVED

NOV 13 2001

KCC WICHITA

NOV 08 2001

WILLIAM B. COLLINS

REPLACEMENT CARD

26-13-20W

#2 YOUNGER "B"

SW NW NW

67601

DREILING OIL, INC.

CTY. ELLIS

GEOL. LAWRENCE F. GRAY

FIELD IRVIN

2200 KB CM 11/29/80

CARD ISSUED 2/19/81

IP OIL WELL

2195 GL

LANS 3491-3673 OA

ARB OH 3842-3845

API 15-051-22,142

COMMINGLED

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
SC	1511	+ 689	
B SC	1556	+ 644	
TOP	3215	-1015	
HEFB	3449	-1249	
TOP	3470	-1270	
LANS	3489	-1289	
BKC	3744	-1544	
MARM	3778	-1578	
ARB	3840	-1640	
RTD	3845	-1645	

8 5/8" 168/135sx; 5 1/2" 3842/150sx

DST (1) 3515-3585/30-45-30-45, 120' GIP, REC 180' M W/FEW OIL SPOTS, SIP 217-205#, FP 79-98/98-128#

DST (2) 3619-3680/30-45-30-45, REC 190' HO & GCM, SIP 395-395#, FP 59-79/98-118#

MICT - CO, (ARB OH), AC500G, PF(LANS) 1/3673, 1/3650, 1/3627, 1/3525, 1/3495, 1/3491, SET RBP @ 3700, AC6000G, PULLED PLUG, POP

CORRECTION: 8/27/81 WAS C E/2 W/2 NW

INDEPENDENT OIL & GAS SERVICE WICHITA, KANSAS