

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21787-00-00  
Spot: CE2NWNW Sec/Twnshp/Rge: 26-13S-20W  
4620 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: YOUNGER B Well Number: 1  
County: ELLIS Total Vertical Depth: 3825 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 168 w/125 sxs cmt  
Production: Size 4.5 feet: 3723 w/150 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/06/2001 11:30 AM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed Plugging Method: Ordered out 145 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/06/2001 1:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 2000' - 1500' - 750'.  
RIH with tubing to 1978' and spotted 60 sxs with 400# hulls.  
Pulled up to 1000' and circulated cement with 60 sxs and 100# hulls.  
POOH. Topped with 20 sxs.  
Hooked onto annulus and pumped 5 sxs with Max. P.S.I. 500#.


Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

10



(TECHNICIAN)

RECEIVED

NOV 13 2001

KCC WICHITA

NOV 08 2001

REPLACEMENT CARD

J. B. COLLINS  
 1007 CODY, SUITE A  
 HAYS, KS 67601

26-13-20W  
 C-E/2 NW-NW

#1 YOUNGER "B"

CONTR DREILING OIL, INC. CTY - ILLIS

GEOL LAWRENCE F. GRAY FIELD IRVIN

E 2185 KB CM 9/26/79 CARD ISSUED 2/14/80P OIL WELL

API 15-051-21,787 TOR 3460  
 LKC 3478-3679-0A

+	+
+	+

LOG	TOPS	DEPTH	DATUM
ANH		1494	+ 691
TOP		3200	-1015
HEEB		3435	-1250
TOR		3456	-1271
LKC		3476	-1291
BKC		3726	-1541
MARM		3766	-1581
TD		3825	-1640

8-5/8" 168/125sx, 4 1/2" 3723/150sx

DST (1) 3443-3495/30-45-30-45, REC NA, SIP 687-472#, FP 70-90/70-90#, HP 1912-1888#

DST (2) 3670-3710/30-30-10-0, REC NA, SIP 57-0#, FP 53-53/53-53#, HP 2048-2040#

MICT - CO, PF 1/3614, 1/3636, 1/3679, 1/3460, 1/3478, 1/3513, 1/3538, AC 4100 GAL, POP

INFO RELEASED: 4/30/81