

6 030415

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-24, 204-00-00-D
LOGGED
SESWNE, SEC. 26, T 13 S, R 20 W E

TECHNICIAN'S PLUGGING REPORT

2970 feet from N/S section line
1650 feet from W/E section line

Operator License # 6272

Lease Name Herman "A" Well # 1

Operator: Corie Oil Co. Inc.

County Ellis 124.96

Name & Address Box 534

Well Total Depth 3845 Normal feet

Russell, Kansas

Conductor Pipe: Size _____ feet

67665

Surface Casing: Size 8 5/8 feet 263'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Big Three Drilg Inc. License Number 5836

Address Gorham Kansas 67640

Company to plug at: Hour: PM Day: 8 Month: 4 Year: 19 85

Plugging proposal received from Stan Kovelady

(company name) Big Three Drilg. (phone) _____

were: 8 5/8" set @ 263' CWC. surf. w/ hole full of no less than 36 vis. mud
and no loss of fluid spot with 4 1/2" drill pipe 215 at 50/50 per 6%
BEL 30cc. w/ 12x Cello Flakes added. Allied Cem. Co.

RECEIVED

STATE CORPORATION COMMISSION

APR 20 1985

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 PM Day: 8 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT Spot 4 1/2" D.P @ 3800' displace 25 cy Cem mix. laydown
D.P. to 1500' displace 25 cy. Cem mix. laydown D.P. to 725' displace 90 cy.
Cem. mix. laydown D.P. to 265' displace 40 cy. Cem. mix. laydown
D.P. Push W.P. to 40' fill hole with Cem. mix. to bottom cellar.
Displace 15 cy Cem. mix in rat hole and 10 cy Cem mix. in mouse hole.
plug down @ 5:30 PM Plugging Complete.

Remarks: Class 2177 KB only 1485-1532 next to marmaton Production
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 5-7-85

Signed Carl Goodnow
(TECHNICIAN)

INV. NO. 7961

10
4-26-85