

9-26
API NUMBER 15- 051-21,186 -00-00

To: 6 061959
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE, SEC. 26, T 13 S, R 20 W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
4047
Operator License #
Operator: Sterling Petroleum Oper Co.
Name & Address: 112 S. Broadway
Sterling, Ks. 67579

Lease Name Herrman Est. # 1
County Ellis 123.76
Well Total Depth 3808 PB feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00 AM Day: 26 Month: Sept Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 250 sks 60/40 poz 8% gel 5 sks hulls.

Arb plug at 3806 w/25 sks.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 PM Day: 26 Month: September Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 218' w/105 sks. 4 1/2" set at 3806' w/175 sks. Top perf at 3448'. Plugged bottom w/sand and 4 sks cement to 3400'.

Shot pipe one time and recovered no. Pumped in 4 1/2" 25 sks cement followed w/5 sks hulls in 215 sks cement w/800 psi. 8 5/8" 10 sks cement w/300 psi. Had leak at surface. Called out Weller to fix leak. By Allied.

STATE RECEIVED CORPORATION

Remarks: Ran line to 3300'. Shot hole at 1600' to plug.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed *Gilbert G. Scheck*
(TECHNICIAN)

INVOICED
DATE 10-26-89
INV. NO. 26245