

To: 1 031381
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-23,916-0000
NW SW SW, SEC. 35, T 17 S, R 25 W/E
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 31389 1-31
Operator: Noble Petroleum, Inc.
Name: 3101 N. Rock Rd., Ste. 125
Address: Wichita, KS 67226

Lease Name Krug Well # 1
County Ness
Well Total Depth 4403 143.10 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 31 Month: 1 Year: 1996

Plugging proposal received from Rich Wheeler
(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1659-1681'
1st plug at 1680' with 50 sx cement, 2nd plug at 740' with 70 sx cement,
3rd plug at 300' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:45 a.m. Day: 31 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 1680' with 50 sx cement,
2nd plug at 740' with 70 sx cement,
3rd plug at 300' with 50 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel # floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If not observed, observe this plugging.)

DATE 2-6-96

INV. NO. 44821

1-31

Signed Steve Durrant (TECHNICIAN)

RECEIVED
KANSAS CORP. COMM
1996 FEB -5 A 9:00

FOR USE

EFFECTIVE DATE: 11-14-95

DISTRICT #

STATE

State of Kansas

135-23,916-0000

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 10, 1995

Spot NW SW SW Sec 35 Twp 17S S. Rg 25W East West

OPERATOR: License # 31389 NOBLE PETROLEUM, INC. 3101 North Rock Road - Suite 125 Wichita, Kansas 67226

CONTRACTOR: License # 5929 DUKE DRILLING CO., INC.

Well Drilled For: Well Class: Type Equipment: X Oil ... Enh Rec X Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... OWD ... Disposal ... Wildcat ... Cable ... Seismic: ... # of Holes ... Other

Directional, Deviated or Horizontal wellbore? ... yes X no If yes, true vertical depth: Bottom Hole Location Exp. 5/9/96

990 feet from South / North line of Section 4950 feet from East / West line of Section IS SECTION X REGULAR IRREGULAR (NOTE: Locate well on the Section Plat on Reverse Side) County: Ness Lease Name: POTTER H.A.G. Well #: 1 Field Name: Is this a Propped/Spaced Field? ... yes X no Target Formation(s): Lans, Miss Nearest lease or unit boundary: 330' Ground Surface Elevation: feet MSL Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no Depth to bottom of fresh water: 180' Depth to bottom of usable water: 700' Surface Pipe by Alternate: 1 X 2 275' Length of Surface Pipe Planned to be set: Length of Conductor pipe required: N/A Projected Total Depth: 4350 Formation at Total Depth: Mississippi Water Source for Drilling Operations: well farm pond X other OWR Permit #: Will Cores Be Taken? ... yes X no If yes, proposed zone: 200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

AFFIDAVIT

Pusher Square P/O Richard Wheeler SPUD DATE 1-22-96 INIT. RS LENGTH SURFACE PLANNED 250'

RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 5/8" @ 269 CONDUCTOR ANHYDRITE T-1652 B-1681 ELEVATION TD 4403 FORMATION 27155

RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Ing./Council @ Ft. W/ SX Anhydrite Base @ 1680 Ft. W/ 50 SX 1/2 Base Anyh. @ 240 Ft. W/ 70 SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 320 Ft. W/ 50 SX 40' Plug @ 42-0 Ft. W/ 10 SX RAT HOLE CIRC/W/ SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling X) TECHNICIAN S/D DATE 1-26-96 TYPE OF CEMENT 60/40 Poz 60/90 20/80 RECEIVED KANSAS CORP COMM 6/14/96 RECEIVED KANSAS CORP COMM 1-31-96 STARTING TIME (AM/PM) DATE (AM/PM) DATE 1-31-96 CEMENT COMPANY Applied