

1060214

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,551-0000

C SW NE, SEC. 2, T 17 S, R 26 W XX

1980 feet from N/SX section line

1980 feet from XXE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5110

Lease Name Dumler Well # 1

Operator: B & B Drilling, Inc.

County Ness

Name & Address 501 Union Center

Well Total Depth 4510 142.07 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor B & B Drilling, Inc. License Number 5110

Address 501 Union Center, Wichita, KS 67202

Company to plug at: Hour: 6:00 pm Day: 7 Month: April Year: 19 84

Plugging proposal received from John Armbruster

(company name) B & B (phone) 316-923-4563

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1920' with 50 sx cement

2nd plug at 960' with 50 sx cement

3rd plug at 360' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 pm Day: 7 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1920' with 50 sx cement, 2nd plug at 960' with

50 sx cement, 3rd plug at 360' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement; 6th plug to circulate rathole with

15 sx cement

RECEIVED STATE CORPORATION COMMISSION

APR 12 1984

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthie (TECHNICIAN)

INVOICED (copy) did not observe this plugging.

DATE 4-12-84

INV. NO. 1134