

1 030754

API NUMBER 15-135-23,064-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SW SEC. 2, T 17 S, R 21 W/EX
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6331 & 5146

Lease Name Elmore Well # 1-2

Operator: Taurexco, Inc. & Rains & Williamson

County Ness 136.50

Name & Address Co., Inc.

Well Total Depth 4200 feet

125 N. Market, Suite 1210

Conductor Pipe: Size _____ feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Rains & Willaimson Oil Co., Inc. License Number 5146

Address 435 Page Court, 220 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 3 p.m. Day: 4 Month: 11 Year: 19 86

Plugging proposal received from Mike Godfrey

(company name) Rains & Willaimson Oil Co., Inc. (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at base Anhydrite with 50 sx cement, 2nd plug at 50' base Cheyenne with 80 sx cement, 3rd plug at 30' below base of surface pipe with 40 sx cement, 4th plug at 40-0' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 p.m. Day: 4 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement,

2nd plug at 750' with 80 sx cement,
3rd plug at 460' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

NOV 6
11-06-1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If not, observe this plugging.)

DATE 11-7-86

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 15305

11-4

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 10 - 24 - 86 month day year

API Number 15- 135-23,064-00-00

OPERATOR: License # 6331 & 5146 Name Taurexco, Inc. & Rains & Williamson Oil Co., Inc. Address 125 N. Market, Suite 1210 City/State/Zip Wichita, KS 67202 Contact Person Thomas C. Hyde Phone 316/262-8339

NW NW SW Sec. 2 Twp. 17 S, Rg. 21 East West Lease Name Elmore Well # 1-2 Ground surface elevation Ft. from South Line of Section 2310 Ft. from East Line of Section 4950

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Ness

CONTRACTOR: License # 5146 Name Rains & Williamson Oil Co., Inc. City/State Wichita, KS

Lease Name Elmore Well # 1-2 Ground surface elevation Ft. MSL

Well Drilled For: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no Lease Name Elmore Well # 1-2 Ground surface elevation Ft. MSL

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Municipal well within one mile: yes no Depth to bottom of fresh water 50' Depth to bottom of usable water 800' 700'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 10-15-86 Signature of Operator or Agent Mark K. Mays Title Vice President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. 48 This Authorization Expires 4-15-87 Approved By 10-15-87

Spud 10-28- Set 400'

NW NW SW Sec. 2 Twp. 17 S, Rg. 21 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug #, Depth (ft), Depth (ft), and Cement (sxs). 1st plug @ 1500 feet depth with 30 sxs of cement. 2nd plug @ 800 feet depth with 75 sxs of cement. 3rd plug @ 400 feet depth with 30 sxs of cement. 4th plug @ 40 feet depth with 10 sxs of cement. 5th plug @ 15 feet depth with sxs of cement. (2) Rathole with 15 sxs (b) Mousehole with sxs

Form with columns: PUSHER (Mike Godfrey), TD, SURFACE PIPE @, ANHYDRITE, ELEVATION, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ Base w/ 50 SX, 2nd PLUG @ 50' Base w/ 80 SX, 3rd PLUG @ 30' Base w/ 40 SX, 4th PLUG @ 40-0 FT. w/ 10 SX, RAT HOLE CIRCULATED w/ 15 SX, MOUSE HOLE CIRCULATED w/ SX, WATER WELL PLUGGED w/ Pond - SX, CEMENT COMPANY, TECHNICIAN (SQ), NOV 6 1986, 11-06-1986