

6-28 15:051:00434:00:00

6 010621

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Old Well

NW NW SW, SEC. 32, T 13 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT 5465

2310 feet from S section line

4950 feet from E section line

Operator License #

Lease Name Anthony Kuhn Well # 1

Operator: B J Oil Co.

County Ellis 112.91

Name & Address 1503 Vine Suite B

Well Total Depth 3474 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 196

Abandoned Oil Well  Gas Well  Input Well  SWD Well  U&A

Other well as hereinafter indicated

Plugging Contractor B J Oil Co. License Number 5465

Address Hays, Ks.

Company to plug at: Hour: 10:00AM Day: 28 Month: June Year: 19 88

Plugging proposal received from J. B. Collins

(company name) B J Oil Co. (phone)

were: Order 300 sks cement 65/35 Pozmix 10% Gel ATL - 500#. Hulls. 5 1/2" at 3474 w/150 sks. Squeezed 593' - 694' w/400 sks Anhydrite 1035' - 1085'.

RECEIVED STATE CORPORATION COMMISSION

OCT 21 1988

Shot at 1060' Fluid level at 1500'. Ran line. Perf at 3255' - 3389'.

Plugging Proposal Received by D. F. B. (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: Day: 28 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Pumped down 5 1/2" casing 50 sks cement then 175 sks cement w/500# Hulls. Max pres 600#. Closed w/300#. Pumped down 8 5/8" 50 sks cement w/100# Hulls. Max pres 400#. Closed w/300# pres.

Remarks: Allied Cement C. (If additional description is necessary, use BACK of this form.)

INVOICED (If desired, observe this plugging.)

DATE 10-24-88

INV. NO. 22658

Signed Dale F. Balthazor (TECHNICIAN)

Dale F. Balthazor