

To: 1 051168
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-29
API NUMBER 15-093-20,980 0000
C NW SW, SEC. 16, T 26 S, R 35 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003
Operator: McCoy Petroleum Corporation
Name & Address 110 South Main, Suite 500
Wichita, KS 67202

1980 feet from S section line
4620 feet from E section line
Lease Name White Well # 1-16
County Kearny 172.32
Well Total Depth 5302 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1878

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hayes Well Service License Number 5429
Address P.O. Box 108, Attica, KS 67009

Company to plug at: Hour: 10 a.m. Day: 29 Month: 4 Year: 19 89

Plugging proposal received from Darryl Hanson
(company name) McCoy Petroleum (phone) 316-265-9697

were: 5 1/2" at 4610' PBD 4452' Perfs at 4432-36' TOC 3500'
1st plug set CIBP at 4400' and dump 2 sx cement on top of sand through bailer,
2nd plug pump 100 sx cement at 2800', 3rd plug pump 50 sx cement at 1900',
4th plug pump 40 sx cement at 1000',
5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:30 p.m. Day: 29 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4400' with 2 sx cement,
2nd plug at 2817' with 100 sx cement,
3rd plug at 1947' with 50 sx cement,
4th plug at 1006' with 40 sx cement,
5th plug at 62' with 13 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1989

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If not observed this plugging.)

DATE 5-8-89

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 24638