

To: 1052011  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
101 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 135-23,919-00-00  
NW SE NE, SEC. 34, T 16 S, R 22 W/E  
1650 feet from N S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

2-7

Operator License # 4767  
Operator: Ritchie Exploration, Inc.  
Name:  
Address 125 N. Market, Ste. 1000  
Wichita, KS 67202

Lease Name Walker "A" Well # 2  
County Ness  
Well Total Depth 4420 143,65 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 213

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling License Number 5420  
Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: \_\_\_\_\_ Day: 7 Month: 2 Year: 19 96

Plugging proposal received from Judy  
(company name) White & Ellis Drilling (phone) 316-263-1102

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1683-1717'  
1st plug at 1710' with 50 sx cement, 2nd plug at 1030' with 80 sx cement,  
3rd plug at 500' with 40 sx cement, 4th plug at 240' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:45 p.m. Day: 7 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1710' with 50 sx cement,  
2nd plug at 1030' with 80 sx cement,  
3rd plug at 500' with 40 sx cement,  
4th plug at 240' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

RECEIVED  
KANSAS CORPORATION COMMISSION  
02-09-1996  
FEB 09 1996

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED (XXX) did not observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

DATE 2-28-96  
INV. NO. 44908  
2-7

EFFECTIVE DATE: 1-2-96

State of Kansas

NOTICE OF INTENTION TO DRILL

135-23;919-00-00

DISTRICT #

SGAT Yes X No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 1 5 96 month day year

Spot NW SE NE Sec 34 Twp 16 S. Rg 22W East West

OPERATOR: License # 4767 Name: Ritchie Exploration, Inc. Address: 125 N. Market, Suite 1000 City/State/Zip: Wichita, KS 67202 Contact Person: Lisa Thimmesch Phone: (316) 267-4375

1650 feet from South / North line of Section 990 feet from East / West line of Section THIS SECTION X REGULAR IRREGULAR

CONTRACTOR: License #: 5420 Name: White & Ellis Drilling

(NOTE: Locate well on the Section Plat on Reverse Side) County: Ness Lease Name: Walker "A" Well #: 2

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec X Infield X Mud Rotary Gas Storage Pool Ext Air Rotary OWWO Disposal Wildcat Cable Seismic: # of Holes Other If OWWO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Is this a Prorated/Spaced Field? yes X no Target Formation(s): Mississippi

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location: Exp. 6/28/96

Nearest lease or unit boundary: 990' Ground Surface Elevation: 2362 est.

Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 180

Depth to bottom of usable water: 1020

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 200

Length of Conductor pipe required: none

Projected Total Depth: 4450

Formation at Total Depth: Mississippi

Water Source for Drilling Operations: well farm pond X other

DWR Permit #: Will Cores Be Taken? yes X no

If yes, proposed zone:

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met.

Pusher: Judy SPUD DATE: 1-29-96 INIT. QW LENGTH SURFACE PLANNED: 200' RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLE AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/8" @ 2 1/2" CONDUCTOR ANHYDRITE T-1683 B-1212 ELEVATION TD 4420 FORMATION Miss RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 1710 Ft. W/ 50 SX 1/2 Base Anyh. @ 1030 Ft. W/ 80 SX 1/2, 1/2 Plug @ 500 Ft. W/ 40 SX Bottom Surface 240 Ft. W/ 40 SX 40' FT. W/ 10 SX TRAT HOLE @ MOUSE HOLE W/ SX WATER WELL (Irr. Well Pond Hauling) TECHNICIAN DATE 1-31-96 TYPE OF CEMENT 60/40 p02 6' shot 1/4 Flag STARTING TIME (AM/PM) DATE COMPLETION TIME 11:45 (AM/PM) DATE 2-2-96 CEMENT COMPANY

RECEIVED KANSAS CORPORATION COMMISSION FEB 09 1996