

1 090261

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW NW NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,662-00-00 *R*

4290 feet from X section line
2310 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Ummel Well # 1

Operator: A. Scott Ritchie

County Ness

Name & Address 125 North Market, Suite 950

Well Total Depth 4433 144.07 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 8 Month: September Year: 19 84

Plugging proposal received from Bud Wenrich

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1710' with 50 sx cement

2nd plug at 930' with 50 sx cement

3rd plug at 330' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by RBFarhatten
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 pm Day: 8 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1710' with 50 sx cement, 2nd plug at 930' with 50 sx cement, 3rd plug at 330' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied # 27806

12-18-1984
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 12-22-84

Signed RBFarhatten
(TECHNICIAN)

INV. NO. 6173