

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24152-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 24-16S-22W
2310 feet from N Section Line, 2060 feet from E Section Line
Lease/Unit Name: RYAN Well Number: 1-24
County: NESS Total Vertical Depth: 4304 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 155 N. MARKET, STE. 1020
WICHITA, KS 67202

Conductor Pipe: Size feet: 8/39.85
Surface Casing: Size 8.625 feet: 222
Production: Size 5.5 feet: 4298 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/12/2002 11:50 AM
Plug Co. License No.: 5316 Plug Co. Name: FALCON EXPLORATION, INC.
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (316) 262-1378

Proposed Method: SAND TO 4200' & 5 SX CMT. 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 1000' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/12/2002 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4285-4289 & 4248-4253'. SANDED TO 4180' & 5 SX CMT ON TOP OF SAND. 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 1000' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 25 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 26 2002
02-26-2002
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2385' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

FEB 14 2002

INVOICED
DATE Feb 20 02
INV. NO. 2002061416