

1 110082

9-30-87

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3156

Operator: Alligator-19 Oil Company

Name & Address 215 East 5th

Hays, KS 67601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Dreiling Oil, Inc. License Number 5145

Address R R 1, Box 1000, Victoria, KS 67671

Company to plug at: Hour: 5:45 a.m. Day: 30 Month: 9 Year: 19 87

Plugging proposal received from Everett Michelson

(company name) Dreiling Oil, Inc. (phone) 913-735-2204

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2340' KB
Anhydrite 1656-99'

1st plug at 1700' with 50 sx cement, 2nd plug at 850' with 80 sx cement,

3rd plug at 230' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8:50 a.m. Day: 30 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1700' with 50 sx cement,

2nd plug at 850' with 80 sx cement,

3rd plug at 230' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
 did not observe this plugging.

DATE 10-6-87

INV. NO. 18367

Signed James R. Kapp
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1987

CONSERVATION DIVISION
Wichita, Kansas

10-02-1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. SEPT. 15 1987 month day year

API Number 15-135-23,160-22500

OPERATOR: License # 03156 Name ALLIGATOR-19 OIL CO. Address 215 E. 5th City/State/Zip HAYS, KANSAS 67601 Contact Person RON NELSON Phone 913-628-3449

NE NW NW Sec. 24 Twp. 16 S. Rg. 22 West 4950 Ft. from South Line of Section 4290 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5145 Name DREILING OIL, INC. City State VICTORIA, KANSAS

Nearest lease or unit boundary line 330 feet County NESS Lease Name RYAN "B" Well # 1 Ground surface elevation N.A. feet MSL Domestic well within 330 feet: yes no Municipal well within one mile: yes no Depth to bottom of fresh water 1007 Depth to bottom of usable water 850 app. Surface pipe by Alternate: 1 2 Conductor pipe required NONE Projected Total Depth 4400 feet Formation MISSISSIPPI

Well Drilled For: Well Class: Type Equipment: Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 8-26-87 Signature of Operator or Agent Title PARTNER

For KCC Use: Conductor Pipe Required 2-26-88 feet; Minimum Surface Pipe Required 200 feet per Alt. This Authorization Expires 2-26-88 Approved By 8-26-87

Move in 9-23-87 set 8 1/8 200'

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. BASE ANHYDRITE or formation with 50sks feet of 60-40 poz 3%-2% 2nd plug @ ft. deep. BASE DAKOTA or formation with 75sks feet of 3rd plug @ ft. deep. 50' BELOW SURE PIPE or formation with 50SKS feet of 4th plug @ ft. deep. 40' or formation with 10sks feet of 5th plug @ ft. deep or formation with 10sks feet of (2) Rathole to surface minus 5 feet 10sks (b) Mousehole to surface minus 5 feet

PUSHER Everett Michaelson TD 4380 FORMATION Mead SURFACE PIPE 208' @ 8 1/8 135 SX ANHYDRITE 1656 ELEVATION 2340 KB STARTING TIME & DATE 9/30/87 5:45AM COMPLETION TIME & DATE 9/30/87 8:50 AM 1st PLUG @ 1700 FT. W/ 50 SX 2nd PLUG @ 850 FT. W/ 80 SX 3rd PLUG @ 230 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ Hand water CEMENT COMPANY Allied TECHNICIAN 60/40 Poz 670 Amp

RECEIVED STATE CORPORATION COMMISSION OCT 2 1987 10-02-1987 CONSERVATION DIVISION Wichita, Kansas