

15-135-21275-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

NESS County. Sec. 11 Twp. 17SRge. 21W E/W  
Location as "NE/CNW/SW" or footage from lines  
NE NE

Lease Owner A SCOTT RITCHIE  
Lease Name VAN WINKLE Well No. 1  
Office Address 125 N MARKET, SUITE 950, WICHITA, KS.  
Character of Well (Completed as Oil, Gas or Dry Hole)  
DRY HOLE



Locate well correctly on above  
Section Plot

Date Well completed DECEMBER 29 1976  
Application for plugging filed DECEMBER 29 1976  
Application for plugging approved DECEMBER 29 1976  
Plugging commenced DECEMBER 29 1976  
Plugging completed DECEMBER 29 1976

Reason for abandonment of well or producing formation  
TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO F MASSEY  
Producing formation Depth to top Bottom Total Depth of Well  
Show depth and thickness of all water, oil and gas formations.

RECEIVED  
OIL, GAS OR WATER RECORDS  
CORPORATION COMMISSION  
Wichita, Kansas

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
JAN 13 1977 01-13-1977				8 5/8"	324.08'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD TO 500'. SET  
PLUG. PUT IN 50 SACKS CEMENT. FILLED  
WITH HEAVY MUD TO 240'. SET PLUG.  
PUT IN 25 SACKS CEMENT. FILLED WITH  
HEAVY MUD TO 40'. SET PLUG. FILLED  
TO TOP WITH 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor C-G DRILLING CO.  
1107 DOUGLAS BUILDING, 104 SOUTH BROADWAY, WICHITA, KANSAS 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss:  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway  
1107 Douglas Building, Wichita, Ks.  
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 29th day of Decmeber 1976

My commission expires March 3, 1980  
Debra Heersche Notary Public.



OUR NEW ADDRESS:  
C-G DRILLING CO.  
1107 DOUGLAS BLDG.  
104 SOUTH BROADWAY  
WICHITA, KANSAS 67202  
263-1793

15-135-21275-00-00

OUR NEW ADDRESS:  
C-G DRILLING CO.  
1107 DOUGLAS BLDG.  
104 SOUTH BROADWAY  
WICHITA, KANSAS 67202  
263-1783

W E L L L O G

OPERATOR: A SCOTT RITCHIE  
WELL NAME: VAN WINKLE #1 LOCATION: NE NE SEC 11-17S-21W  
COUNTY: NESS STATE: KANSAS  
WELL COMMENCED: DEC. 16, 1976 WELL COMPLETED: DEC. 29, 1976  
ELEVATION: 2190 KB TOTAL DEPTH: 4122  
PRODUCTION: DRY & ABANDONED RIG NO: 1  
CASING - 8-5/8": 9 JOINTS USED 28# SET 324.08' W/175 SX CEMENT  
±2% GEL + 3% CA CL  
5-1/2": \_\_\_\_\_

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	925	SHALE & SAND		
925	1140	SAND		
1140	1429	RED BED & SHALE		
1429	1490	ANHYDRITE		
1490	1855	SHALE		
1855	2130	SHALE & SHELLS		
2130	3640	LIME & SHALE		
3640	4122	LIME		DST #1 4066'-4095' 30-30 GOOD BLOW TO WEAK INTERMITTENT BLOW. REC 130' MUD W/SPOTS OIL IBHP 138# FBHP 562# FFP 183#
	4122	RTD		DST #2 4066'-4095' 30-45-45-60 FAIR BLOW. REC 390' WATER W/ SCUM OIL. IBHP 517# FBHP 517# IFP 46# FFP 230#
				DST #3 4104'-4122' 30-30-30-30 REC 40' MUD IBHP 160# FBHP 126# IFP 57# FFP 69#

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1977  
01-13-1977  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This G. F. Galloway 6th day of January, 1977.

MY COMM. EXP. DEC. 8, 1979

Phyllis Buchanan  
PHYLLIS BUCHANAN - NOTARY PUBLIC

