

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-135-23,466-00-00

LEASE NAME Yawger

WELL NUMBER 1

1400 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 6 TWP. 17 SRGE. 21 (X) (X) (X) (W)

COUNTY Ness

Date Well Completed 5/30/90

Plugging Commenced 6/1/90

Plugging Completed 6/1/90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, #801, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/30/90 & 6/1/90 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
 STATE CORPORATION COMMISSION  
06-20-1990  
WV 26 1990  
 CONSERVATION DIVISION  
 Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	332 50	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Filled hole w/heavy mud to 1580'; 1st plug @ 1580' to 1260' w/80 sxs; 2nd plug @ 920' to 600' w/80 sxs; 3rd plug @ 380' to 180' w/50 sxs; 4th plug from 40' to surface w/10 sxs; 15 sxs. in rathold. All cement 60/40 pozmix w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, #801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) Jack K. Wharton  
150 N. Main, #801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 90

DEBORAH K. AMMERMAN  
 Notary Public - State of Kansas  
 My Appt. Expires 3-1-92

Deborah K. Ammerman  
 Notary Public

Commission Expires: 3-1-92

ABERCROMBIE DRILLING, INC.

801 UNION CENTER  
WICHITA, KANSAS 67202

A. L. Abercrombie, Inc.  
150 N. Main, #801  
Wichita, KS 67202

YAWGER #1  
App. SW NW SE  
Sec. 6-17S-21W  
Ness County, KS

CONTRACTOR: Abercrombie Drilling, Inc.  
SURFACE: 8 5/8 @ 332.50 w/200 sxs.

DRILLERS WELL LOG

05-22-90	0 to 225	Sand and Shale
05-23-90	225 to 780	Sand and Shale
05-24-90	780 to 1542	Sand and Shale
	1542 to 1576	Anhydrite
	1576 to 1635	Sand and Shale
05-25-90	1635 to 2315	Sand and Shale
	2315 to 2560	Shale
05-56-90	2560 to 3010	Shale
	3010 to 3245	Shale and Lime
05-27-90	3245 to 3435	Lime and Shale
	3435 to 3820	Shale and Lime
05-28-90	3820 to 4075	Shale and Lime
	4075 to 4195	Lime and Shale
05-29-90	4195 to 4260	Lime and Shale
	4260 to 4350	Shale and Lime
	4350	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

JUN 26 1990

CONSERVATION DIVISION  
Wichita, Kansas