

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Ness

County. Sec. 14 Twp. 17 Rge. (E) 21 (W)

Location as "NE/CNW&SW" or footage from lines NE NE SE

Lease Owner Iron Drilling Company

Lease Name Higgins Well No. 1

Office Address 1206 Philtower Building, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1/4/56 19

Application for plugging filed 1/4/56 19

Application for plugging approved 1/4/56 19

Plugging commenced 1/4/56 19

Plugging completed 1/4/56 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation none Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3581		8-5/8"	279	None
Toronto		3599				
Lansing		3624				
Marmaton		3926				
Cherokee		4079				
Conglomerate		4143				
Arbuckle		4264				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 275 feet. Set bottom plug with 25 sacks of cement and 1/2 sack of Hulls. Filled hole and set top plug at 35 feet using 10 sacks of cement and 1/2 sack of hulls. Filled hole to bottom of cellar with cement.

01-19-1956

Name of Plugging Contractor Iron Drilling Company
Address 1206 Philtower Building, Tulsa, Oklahoma.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
J. L. Stackpole (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Stackpole

(Address) _____

18th day of January, 1956

Subscribed and Sworn to before me this



Feb. 28, 1956

B. Michal
Notary Public.

PLUGGING
FILE SEC 14 T 17 R 21W
BOOK PAGE 29 LINE 37

Rec'd
12-19-1954

15-135-00089-00-00

DRILLING RECORD

Well #1 - Higgins
NE NE SE Section 14-17S-21W
Ness County, Kansas

Casing Record

279' - 8-5/8" OD Surface Casing
cemented w/ 150 sacks of
cement.

Work Commenced 12/18/55
Drilling Commenced 12/15/55
Drilling Completed 1/4/56
Work Completed 1/4/56

Dry Hole - No Oil String.

Well Log

Top Soil & Clay	0' to 70'
Shale	70' to 282'
Shale & Shells	282' to 1440'
Anhydrite	1440' to 1473'
Shale & Shells	1473' to 1995'
Shale & Lime	1995' to 2385'
F. R. Lime	2385' to 2400'
Lime & Shale	2400' to 2565'
Lime	2565' to 2630'
Lime & Shale	2630' to 3672'
Lime	3672' to 3993'
Lime & Chert	3993' to 4009'
Lime	4009' to 4044'
Lime & Shale	4044' to 4075'
Lime	4075' to 4089'
Lime & Sand	4089' to 4110'
Conglomerate	4110' to 4156'
Cherty Conglomerate	4156' to 4208'
Lime & Shale	4208' to 4234'
Shale & Cherty Lime	4234' to 4249'
Lime & Shale	4249' to 4265'
Arbuckle Lime	4265' to 4291' TD


State of Oklahoma, County of Tulsa, ss

J. L. Stackpole employee of the Iron Drilling Company
being first duly sworn on oath says: That I have
knowledge of the facts, statements and matters herein
contained and the log of the above-described well as
filed and that the same are true and correct.
So Help me God.

PLUGGING
FILE SEC 14 J 17 R 21W
BOOK PAGE 29 LINE 27

J. L. Stackpole

Subscribed and sworn to before me this 18th day of
January, 1956.



P. Michal
Notary Public

My Commission expires Feb. 28, 1956