


WELL PLUGGING RECORD

Give All Information Completely
*Make Required Affidavit
*Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Ness County, Sec. 14 Twp. 17S Rge. 21 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Pickrell Drilling Company
Lease Name Conner Well No. B-1
Office Address 705 Fourth Nat'l Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 8-8-67 19
Application for plugging approved 8-9-67 19
Plugging commenced 8-14-67 19
Plugging completed 8-18-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well PBL1149 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	261	None
				5 1/2	None	2615

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Rigged up.

Sanded back from 4179' to 4100'. Mixed and dumped 5 sacks of cement on sand bridge at 4100'. Dug out cellar. Rigged up jacks. Shot pipe at 3351'. Working pipe.

Shot pipe at 3022'. Working pipe. Shot pipe at 2819'. Working pipe.

Shot pipe at 2610'. Working pipe. Pulling pipe.

Globe Cementing plugged well with 100 sacks of cement and 30 sacks of mud.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1967
08-24-1967

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc. CONSERVATION DIVISION
Address P. O. Box 221 Great Bend, Kansas WICHITA, KANSAS

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of August, 1967

My commission expires May 27, 1969

Notary Public.

ROTARY DRILLING LOG

15-135-20002-00-00

COMPANY: **Pickrell Drilling Company**
 705 Fourth National Bank Bldg.
 Wichita, Kansas

LOCATION: **Conner "B" No. 1**
 C SW SW Section 14-17S-21W
 Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

Rotary Drilling Commenced 1/9/67

Rotary Drilling Completed 1/19/67

CASING RECORD: (12 jts.) 8 5/8" surface casing set at 261' and cemented with 160 sacks cement. Circulated. (130 jts.) 5 1/2" casing set at 4176' and cemented with 100 sacks cement. Completed at 7:40 PM, January 19, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Surface Soil & Clay	<u>C. F. S.</u>
261	Shale & Shells	4100
520	Shale	4113
860	Shale & Shells	4117
1150	Sand	4172
1395	Shale, Shells & Red Beds	4179
1460	Shale & Shells	
1495	Anhydrite	
1785	Shale, Shells & Salt	<u>Slope Tests</u>
2440	Lime & Shale	
2547	Lime	2500
2790	Lime & Shale	3000
3005	Shale & Lime Stringers	3500
3180	Shale & Some Lime	4000
3970	Lime & Shale	
4100	Lime	
4117	Shale & Sand	<u>S. L. M.</u>
4137	Sand	3874'
4172	Shale & Lime	
4179	Mississippian, RTD	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 11 1967
 08-11-1967
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By [Signature]
 C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 24th day of January, 19 67, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
 L. M. Whiting
 Notary Public

