

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-135-20,001-00-00

API NUMBER Drilled 1966

LEASE NAME Elmore "D"

WELL NUMBER 2

1830 Ft. from N Section Line

660 Ft. from E Section Line

SEC. 14 TWP. 17 RGE. 21 (S) or (W)

COUNTY Ness

Date Well Completed 12/30/66

Plugging Commenced 10/20/98

Plugging Completed 10/20/98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Hess Oil Company

ADDRESS P. O. Box 1009, McPherson, KS 67460

PHONE#( 316 241-4640 OPERATORS LICENSE NO. 5663

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/7/98 (date)

by Mike Myer (KCC District Agent's Name).

Is ACO-1 filled?                      If not, is well log attached? card

Producing Formation Cherokee Sd Depth to Top 4094 Ft Bottom                      T.D. 4148 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		284'	0'	8-5/8"	284'	None
Production		4146'	0'	5-1/2"	4146'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged with 210 sacks 60/40 Pozmix, 6% gel and 300# hulls as follows:

Pumped hulls down 5-1/2" casing, then 35 sacks cement. Displaced to

4094' @ 1500 psi. Perforated @ 850' and pumped in 155 sacks. Pressured

to 1000 psi. Pumped 20 sacks cement between 8-5/8" and 5-1/2" casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hess Oil Company License No. 5663

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hess Oil Company

STATE OF KANSAS COUNTY OF MCPHERSON, ss.

Dick Hess

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dick Hess

(Address) same

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 98

My Commission Expires:                     



11-09-1998  
RECEIVED  
KANSAS CORPORATION COMMISSION