

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-135-30272-00-00

API NUMBER Drilled 1966

LEASE NAME Elmore "D"

WELL NUMBER 1

660 Ft. from N Section Line

660 Ft. from E Section Line

SEC. 14 TWP. 17 RGE. 21 (W) or (E)

COUNTY Ness

Date Well Completed 12/8/66

Plugging Commenced 10/20/98

Plugging Completed 10/20/98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Hess Oil Company

ADDRESS P. O. Box 1009, McPherson, KS 67460

PHONE#(316) 241-4640 OPERATORS LICENSE NO. 5663

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/7/98 (date)

by Mike Myer (KCC District Agent's Name).

Is ACO-1 filled? If not, Is well log attached? card

Producing Formation Cherokee Sd Depth to Top 4094 Ft Bottom T.D. 4096 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface Production		402'	0'	8-5/8"	402'	None
		4094'	0'	4-1/2"	4094'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged with 110 sacks 60/40 Pozmix, 6% gel, 300# hulls, and 13 sacks gel as follows: Pumped hulls down 4-1/2" casing, then 25 sacks cement, gel, and 50 sacks cement. Pressured to 1500 psi. Pumped 35 sacks cement down between 4-1/2" and 8-5/8" casing. Pressured to 600 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hess Oil Company License No.

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hess Oil Company

STATE OF KANSAS COUNTY OF MCPHERSON, ss.

Dick Hess

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dick Hess

(Address) same

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 98

My Commission Expires:



11-03-1998
 RECEIVED
 ASSOCIATED
 663
 NOV 3 2 01 35