

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-22171-00-00

LEASE NAME Connors

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 14 TWP. 17S RGE 21W ~~XX~~ or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 1-25-91

Plugging Completed 1-31-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Peak Oil & gas

ADDRESS RR #1 Box 306 McCracken, KS. 67556

PHONE#(913) 394-2596 OPERATOR'S LICENSE NO. 30327

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4205'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD | **RECEIVED** STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	404'	none
				5 1/2"	4205'	2319' CONSERVATION DIVISION Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4080' dumped 5 sacks cement. Shot pipe @3000'
2800, 2600', 2500', 2400', 2319'. Pulled 5 1/2" to 1409' mixed
50 sacks cement, pulled to 700' and mixed 50 sacks pulled to
400' and mixed 45 sacks till circulated top off w/ 20 to surface.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Peak Oil & Gas

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
 statements, and matters herein contained and the log of the above-described well as filed that
 the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 8 day of March, 19 91

Irene Herzberg
 Notary Public

My Commission Expires:



15-135-22171-00-00

Mercury

VARIABLE INTENSITY
CEMENT BOND LOG

COMPANY _____

WELL CONNERS NO. 1

FIELD _____

COUNTY MESS STATE _____

Location _____ Other Services _____

Sec. 14 Twp 17S Rge 21W

Permanent Datum _____ Elev. 2190 Elev. K.B. _____

Log Measured From _____ Ft. Above Perm. Datum D.F. _____

Drilling Measured From _____ G.L. _____

Run No.	01		
Date & Time Survey	12-2-81		
Date & Time Cementing	11-22-81		
Type Cementing Operation			
Depth Driller			
Depth	4160		
Logged Interval	3300	to	4160
Casing Driller	8 5/8	@	404
Float Collar—D.V. Tool			
Squeeze Depth	---		
Amount & Type Cement	---		
Amount & Type Admix	---		
Type Fluid in Hole			
Fluid Level			
Salinity PPM Cl			
Weight lb/gal—Vis.			
Approx. Logged Cem Top			
Calculated Cement Top			
Max. Hole Temperature			
Tool No.	174 29 1001		
Spacing Recorded	3 1/2		
Equipment—Location			
Recorded by	TOM HENDERSON		
Witnessed by			