


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 31 Twp. 11 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C W/2 NW/4 NE/4
Lease Owner Republic Natural Gas Company
Lease Name Hadley Well No. 5
Office Address Box 126, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 22 19 47
Application for plugging filed April 13 19 59
Application for plugging approved April 14 19 59
Plugging commenced April 15 19 59
Plugging completed April 20 19 59
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production September 19 52
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3625' Bottom _____ Total Depth of Well 3700 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1081'	None
				5-1/2"	3658'	2910'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well had been perforated at 3628'. Hole filled with sand from 3700' to 3615'; 4 sacks of cement placed in hole with dump bailer. Pipe shot off at 2900' and pipe pulled to 550'; hole circulated with 16 sacks of cement with Globe Cementing pump trucks and 25 sacks of cement pumped down to 550'; pipe then pulled to 180' and 25 additional sacks of cement pumped down hole; remainder of pipe pulled and hole filled with mud to 40'; rock bridge installed between 40' and 30' and hole capped with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Company
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
P. B. Horst (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

P. B. Horst

Box 126, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 19 59

Y. M. Stevenson

Notary Public.

My commission expires 8-20-59

PLUG LOG
FILE SEC 31 T. 11 R. 17
BOOK PAGE 22 LINE 28

C
O
P
Y

DRILLING LOG

Republic Natural Gas Company
Box 918
Ellinwood, Kansas

Lease: Hadley B #5

County: Ellis, Kansas
Sec. 31-11-17
Location: 330' east of
west line
660' south
of north line

Rotary T. D.: 3702'
Comm: 2-14-47 Comp: 3-10-47
Shot or Treated
Casing: 8" @ 1082' 5 1/2" @ 3700'

Contractor: Gabbert & Lindas
1316 Union National Bank Building
Wichita 2, Kansas

RECEIVED
OIL CORPORATION COMMISSION
APR 14 1959
DIVISION

Figures Indicate Bottom of Formations:

0	to	70	Post Rock	1980	to	2045	Broken Lime
70		100	Sand and Shale	2045		2125	Lime
100		175	Shale	2125		2235	Lime and Shale
175		285	Iron and Shale	2235		2305	Lime
285		575	Shale and Shells	2305		2404	Shale and Lime
575		585	Sand	2404		2460	Lime
585		600	Shale	2460		2545	Shale and Shells
600		685	Shale and Sand	2545		2615	Lime and Shale
685		805	Shale, Shells and streaks of Pyrite	2615		2670	Lime
				2670		2755	Shale and Lime
805		870	Shells	2755		2790	Lime
870		930	Shale and Sand	2790		2870	Shale and Lime
930		1055	Shale and Lime Shells	2870		2881	Shale
1055		1085	Red Bed and Iron	2881		2995	Lime
1085		1340	Red Bed and Shells	2995		3060	Shale and Shells
1340		1345	Red Bed	3060		3125	Lime
1345		1370	Anhydrite	3125		3165	Shale and Lime
1370		1430	Shale and Lime	3165		3496	Lime
1430		1620	Red Bed and Shale	3496		3521	Lime and Shale
1620		1680	Shale and Lime Shells	3521		3605	Lime
1680		1865	Shale and Shells	3605		3638	Conglomerate
1865		1890	Shale	3638		3702	T.D. Arbuckle Lime
1890		1980	Lime				

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath state that the above statement and log is true and correct record and log of the well drilled at the location above described.

GABBERT & LINDAS

By /s/ Scott Stuckey

Subscribed and sworn to before me this 12th day of March, 1947.

/s/ Catherine Darcey
Notary Public

Seal My commission expires Mar. 25, 1948

PLUGGING
FILE SEC. 31 T. 11 R. 17w
BOOK PAGE 29 LINE 28