

15-051-05417-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION CP-4
Rev. 12-15-80

JAN 13 1983

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 31 TWP. 11s RGE. 17w E/W
Location as in quarters or footage from lines:
NW NW NW

Lease Owner Lario Oil & Gas Company

Lease Name Marshall "A" #17 Well No. _____

Office Address 301 South Market, Wichita, Ks. 67202

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 12/22/82

Plugging completed 1/7/83

Reason for abandonment of well or producing formation
Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation _____ Depth to top _____ bottom _____ T.D. 3649'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1363'	none
				5 1/2"	3645'	2846'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged bottom with sand to 3600', & ran 5 sacks cement. Load hole. Shot casing at 2833' & pulled total of 90 joints. Plugged well with 165 sacks 50/50 pos. 4% gel. 3% c.c., 20 sacks gel, 5 hulls, & 8 5/8 plug.

Plugging complete

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 1983

My Commission expires:



Irene Hoover
Notary Public.

MARSHALL NO. 17

15051-05417-0000

Location: NW/4 NW/4 NW/4 Sec. 31-11S-17W
Ellis County, Kansas

Operator: Laric Oil & Gas Company

Contractor: Walters Drilling Co., Inc.

Surface Casing: 8 5/8" set at 1363' with
575 sx cement and 2 C. C.
Recemented top 75' with
40 sx cement

Oil String: 5 1/2" set at 3646' with
100 sx cement

Date Spudded: 10-27-53

Rotary Completion: 11-10-53

Elevation: 2106 Gr
2109 DF
2111 KB

L O G

(Figures indicate bottom of formation)

Shale, Shells and Sand	0 to 248
Shale and Shells	500
Shale and Sand	870
Sand	1060
Shale	1100
Shale and Shells	1285
Shale	1354
Anhydrite	1363
Shale and Shells	1440
Red Bed	1580
Shale and Shells	1765
Shale	1775
Shale and Shells	2112
Lime and Shale	2724
Shale and Shells	2835
Shale	3055
Shale and Shells	3070
Lime and Shale	3165
Lime	3302
Lime and Shale	3425
Lime	3624
Lime and Shale	3649
Total Depth (Rotary)	3649

Geological Tops (Sample)

Topeka	3064
Heebner	3299
Toronto	3317
Lansing-K.C.	3346
Simpson	3597
Arbuckle	3623

Acidized with 500 gals.
Swabbed 16 BOPH for 4 hours.

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO., INC

By Robert F. Walters

Subscribed and sworn to before me
this 16th day of November, 1953.

Pauline Henderson
Notary Public

My commission expires: March 10, 1956

RECEIVED
STATE COMMISSION

FEB 10 1953

CONSERVATION DIVISION
Wichita Kansas