

1 050216

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,510 -00-00

C NW NE , SEC. 32 , T 17 S, R 22 W

660 feet from N/E section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Moore Well # 1-32

Operator: Texas Energies, Inc.

County Ness

Name & Address P. O. Box 947

Well Total Depth 4361 141.73 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 11:00 am Day: 11 Month: May Year: 19 84

Plugging proposal received from Gregg Bailey

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1530' with 50 sx cement

2nd plug at 800' with 40 sx cement

3rd plug at 420' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:00 pm Day: 11 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement, 2nd plug at 800' with 40

sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

INVOICED

DATE 5-21-84

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 1582
5-11