

1-14-88

1 070497

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,209-00-00

SE NE SW, SEC. 3, T 17 S, R 22 W/E

1420 feet from S section line

2980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033 & 3658

Lease Name Horner Well # 1

Operator: Murfin Drilling Co., & M.L. Stone

County Ness 144.95

Name & Address 250 North Water, Suite 300

Well Total Depth 4460 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 389

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 14 Month: 1 Year: 19 88

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2384' Anhydrite 1695-1730'

1st plug at 1730' with 50 sx cement, 2nd plug at 850' with 80 sx cement,

3rd plug at 410' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 14 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1730' with 50 sx cement,

2nd plug at 850' with 80 sx cement,

3rd plug at 410' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 1-15-88

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 19583

FEB 24 1988 MAR 24 1988

RECEIVED STATE CORPORATION COMMISSION 1-15-88 JAN 15 1988 CONSERVATION DIVISION Wichita, Kansas

20

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 1 6 87 88 month day year

API Number 15-135-23, 209-00-00
Approx 150' S of SE NE SW Sec. 3 Twp. 17 S, Rg. 22 W West

OPERATOR: License # 6033 3658
Name Murfin Drilling Co. / M.L. Stone
Address 250 N. Water, Suite 300
City/State/Zip Wichita, Ks. 67202
Contact Person Jack Goss
Phone 316-267-3241

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 320' feet
County Ness

CONTRACTOR: License # 6033
Name Murfin Drilling Company
City/State Wichita, Ks. 67202

Lease Name HORNER Well # 1
Ground surface elevation TBD feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO X Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 150
Depth to bottom of usable water ~900 (Top Permian)
Surface pipe by Alternate: 1-2 X
Surface pipe planned to be set 350'
Conductor pipe required none
Projected Total Depth 4500' feet
Formation Miss

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 12-30-87 Signature of Operator or Agent Jack E. Goss Title Agent for Operator

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 7-1-88 Approved By 12-31-87

EFFECTIVE DATE: 1-5-88
Move 1-6-88 set 8 5/8" 350' NO
Approx 150' S of SE NE SW Sec. 3 Twp. 17 S, Rg. 22 W West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1805 feet depth with 50 sxs of 60/40 P92, .6% gel
2nd plug @ 1100 feet depth with 80 sxs of
3rd plug @ 300 feet depth with 50 sxs of
4th plug @ 40 feet depth with 10 sxs of
5th plug @ feet depth with sxs of
(2) Rathole with 1 sxs (b) Mousehole with sxs

PUSHER R.D. Farr
TD 4460 FORMATION Miss
SURFACE PIPE 6 5/8" @ 389'
ANHYDRITE 1695' ELEVATION 2384'
STARTING TIME & DATE 9:00 am 1-14-88
COMPLETION TIME & DATE 11:15 am 1-14-88
1st PLUG @ 1730 FT. W/ 50 SX
2nd PLUG @ 850 FT. W/ 80 SX
3rd PLUG @ 410 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied 60/40 cement
TECHNICIAN D.G. Sawall

RECEIVED
STATE CORPORATION COMMISSION
1-15-88
JAN 15 1988
CONSERVATION DIVISION
Wichita, Kansas