

1 031285

7-19

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

*API NUMBER 15- 135-23,822-00-00
SE SW SE, SEC. 3, T 17 S, R 22 W/8
330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629

Lease Name Weirman Well # 1-3

Operator: Brito Oil Company, Inc.

County Ness

Name: Address 120 S. Market, Ste. 300

Well Total Depth 4490 145.92 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530-1413

Company to plug at: Hour: _____ Day: 19 Month: 7 Year: 19 94

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling, Inc. (phone) 316-792-5633

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1707-44'
1st plug at 1740' with 50 sx cement, 2nd plug at 870' with 70 sx cement,
3rd plug at 270' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: _____ Day: 19 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1740' with 50 sx cement,
2nd plug at 870' with 70 sx cement,
3rd plug at 270' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (XXXX) / did not) observe this plugging.

DATE 7-27-94

Signed Steve Durrant (TECHNICIAN)

INV. NO. 40879

RECEIVED
STATE CORPORATION COMMISSION
III 25 1994
CONSERVATION DIVISION
WICHITA, KANSAS

EFFECTIVE DATE: 6-22-94

State of Kansas

135-23,822-02-00

FORM MUST BE SIGNED

DISTRICT # 4
SSA7 Yes No

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 7 10 1994
month day year

SE SW SE Sec 3 Twp 17 S. Rg 22 East West

OPERATOR: License # 4629
Name: Brito Oil Company, Inc.
Address: 120 S. Market, Suite 300
City/State/Zip: Wichita, KS 67202
Contact Person: Raul F. Brito
Phone: 316-263-8787

330 feet from South / North line of Section
1650 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5104
Name: Blue Goose Drilling, Inc.

County: Ness
Lease Name: Weirman Well #: 1-3
Field Name: WC

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield ... X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal ... X Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Lansing, Chero, Miss
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2400 est. feet MSL

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 360'
Depth to bottom of usable water: 750'

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth:

Surface Pipe by Alternate: ... 1 X 230'
Length of Surface Pipe Planned to be set: 230'
Length of Conductor pipe required: None
Projected Total Depth: 4450'

Bottom Hole Location:
Exp. 12/17/94

Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well ... farm pond X other

DWR Permit #: ...
Will Cores Be Taken?: ... yes X no
If yes, proposed zone:

AFFIDAVIT

230' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met.

Pusher McTear Miller
SPUD DATE 7-11-94 INIT. SR
LENGTH SURFACE PLANNED 240' of 8 3/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 6 7/8 @ 24 1/2 CONDUCTOR
ANHYDRITE T-1707 B-1744 ELEVATION
TD 4490 FORMATION Miss
RAN PIPE @ 3160 DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 1740 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 870 Ft. W/ 70 SX
1/2, 1/2 Plug @ Ft. W/ SX
3 Bottom Surface @ 270 Ft. W/ 40 SX
4 40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W 10 SX
WATER WELL SX (Irr. Well Pond X)
Hauling
TECHNICIAN SP DATE 7-14-94
TYPE CEMENT 60/40 60/0 # Flow Serv
STARTING TIME : (AM/PM) DATE 7-19-94
COMPLETION DATE : (AM/PM) DATE
CEMENT COMMISSION
RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas
25/1994