

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23872-00-00
Spot: NESWSE Sec/Twnshp/Rge: 1-17S-22W
990 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BARBER Well Number: 1-1
County: NESS Total Vertical Depth: 4350 feet

Operator License No.: 30104
Op Name: CAMBRON, PAUL L.
Address: PO BOX 384 118 N. PENN
NESS CITY, KS 67560

Conductor Pipe: Size feet: 843.50
Surface Casing: Size 8.625 feet: 265 WITH 185 SX CMT
Production: Size 5.5 feet: 4346 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/24/2001 10:15 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MORRIS SMITH Company: Phone: (785) 798-2298

Proposed Plugging Method: PUMP 30 SX CMT & 200# HULLS ON BOTTOM. PUMP 16 SX GEL WITH 48 BBL WATER, THEN 170 SX CMT. PUMP 5 SX CMT DOWN BACKSIDE AND PRESSURE CHECK.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/24/2001 11:20 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4305'. WELL HAS BEEN 2 STAGED AND CMT CIRCULATED. PERFS AT 4198-4202'. PUMP 30 SX CMT & 200# HULLS. PUMP 16 SX GEL WITH 48 BBL WATER. PUMP 170 SX CMT. MAXIMUM PRESSURE 1500#. SHUT IN WITH 800#. TIE ONTO BACKSIDE AND PUMP 5 SX CMT DOWN BACKSIDE. PRESSURE TO 500# AND HELD.

Remarks: USED 60/40 POZMIX 6% GLE BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED

OCT 29 2001

KCC WICHITA

Signed

Michael Maier

(TECHNICIAN)

INVOICED

OCT 26 2001

DATE 10-29-01

INV. NO. 2002060871

Form CP-2/3