

To: 1 051476
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-2
API NUMBER 15-135-23,574-00-00
SW NW SE, SEC. 36, T 16 S, R 25 W/E

255

TECHNICIAN'S PLUGGING REPORT
Operator License # 7261
Operator: Pate-Dombaugh, Inc.
Name & Address 150 N. Main, Suite 804
Wichita, KS 67202-1316

1650 feet from S section line
2310 feet from E section line
Lease Name Ummel Well # 1
County Ness 145.53
Well Total Depth 4478 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Viking Resources, Inc. License Number 5011
Address 105 S. Broadway, Suite 1040, Wichita, KS 67202-4224

Company to plug at: Hour: 8 a.m. Day: 2 Month: 10 Year: 19 91

Plugging proposal received from Terry Richardson
(company name) Viking Resources (phone) 316-262-2502

were: 4 1/2" at 4444', Perfs at 4444-78', Anhydrite 1820-50'
1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,
2nd plug at 1100' with 80 sx cement,
3rd plug at 340' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:35 a.m. Day: 2 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of
sand through bailer,
2nd plug at 1100' with 80 sx cement,
3rd plug at 340' with 50 sx cement,
4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 03 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied. Recovered 1200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-14-91
INV. NO. 33707

Signed Richard M. Lacey
(TECHNICIAN) RL