

1 070520

2-23-88

API NUMBER 15-~~135~~-23081-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NW NE, SEC. 6, T 17 S, R 22 W/E  
4290 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767  
Operator: Ritchie Exploration  
Name & Address: 125 North Market, Suite 1000  
Wichita, KS 67202

Lease Name V. Higgins Well # 1  
County Ness  
Well Total Depth 4470 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Ritchie Exploration License Number 4767  
Address 125 North Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 2:10 p.m. Day: 23 Month: 2 Year: 19 88

Plugging proposal received from Bennie Dills  
(company name) Ritchie Exploration (phone) 316-267-4375

were: 5 1/2" at 4468' PBSD 4439' Perfs at 4304-06', sand out at 4387', hole in pipe at 900'  
Pump plugs through tubing.  
1st plug at 4245' with 200 lbs. hulls and 15 sx cement,  
2nd plug at 1650' with 20 sx cement,  
3rd plug pump 120 sx ATL down 5 1/2",  
4th plug pump 30 sx ATL down 8 5/8".

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:45 p.m. Day: 23 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT Pumped through tubing,

1st plug pumped 200 lbs. hulls and 15 sx 60/40 Pozmix 6% gel at 4245', pressured to 2500, released packer, pulled six joints, pumped 18 sx gel,  
2nd plug spotted 20 sx cement at 1650',  
3rd plug pumped 120 sx ATL cement down 5 1/2" before lost circulation,  
4th plug pumped 30 sx ATL cement down 8 5/8".

Remarks: Used 60/40 Pozmix 6% gel and ATL cement by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION RECEIVED  
MAR - 4 - 88  
3-4-88

INVOICED observe this plugging.  
DATE 3-4-88  
INV. NO. 20020

Signed Dan Goodrow (TECHNICIAN)