

1000389

1-18

API NUMBER 15-135-23,805-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

App. NE NE NW, SEC. 6, T. 17 S, R. 22 W
585 feet from N8 section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444

Lease Name Sargent Well # 1

Operator: Charter Production Co.

County Ness

Name: 140 N. Mosley
Address: 224 E. Douglas, Ste. 400

Well Total Depth 4446 144.50 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 18 Month: 1 Year: 19 94

Plugging proposal received from Duane
(company name) Duke Drilling Co. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1728'
1st plug at 1730' with 50 sx cement, 2nd plug at 920' with 80 sx cement,
3rd plug at 485' with 40 sx cement, 4th plug at 320' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:45 a.m. Day: 18 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1730' with 50 sx cement,
2nd plug at 920' with 80 sx cement,
3rd plug at 485' with 40 sx cement,
4th plug at 320' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 21 1994

INV. NO. 39747

1-18

Signed [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1994
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 1-15-94

State of Kansas
NOTICE OF INTENTION TO DRILL

135-23,805-00-00

DISTRICT # 1

Must be approved by the K.S.C. five (5) days prior to commencing well

Expected Spud Date 12 94 month day year

NE NW Sec 6 Twp 17 S. Rg 22 East

OPERATOR: License # 30444
Name: Charter Production Company
Address: 224 E. Douglas Suite 400
City/State/Zip: Wichita, KS 67202
Contact Person: Jerald W. Rains
Phone: (316) 263-4906

585 feet from South / North line of Section
2970 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License # 5929
Name: Duke Drilling Company

County: Ness
Tract Name: Sargent
Field Name: Development

Well Drilled For: Well Class: Type Equipment:
X Oil ... Erk Rec ... Infield ... Mud Rotary
Gas ... Storage ... Pool Ext. ... Air Rotary
GWWO ... Disposal ... Wildcat ... Cable
Solids: ... # of Holes ... Other

Is this a Perated/Spaced Field? yes X no
Target Formation(s): Cherokee
Nearest lease or unit boundary: 330'

If OAS: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Ground Surface Elevation: 2368 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:
Exp. 7/10/94

Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 280' 900'
Surface Pipe by Alternate: 1 X 2 3
Length of Surface Pipe Planned to be set: 275'

Length of Conductor pipe required:
Projected Total Depth: 4450'
Formation at Total Depth: MIP
Water Source for Drilling Operations:
... well X farm pond ... other

DIR Permit #:
Will Corrosion Be Taken? yes X no
If yes, proposed date:

RECEIVED
KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55.

Pusher: Runc Chic
SPUD DATE: 1-11-94 INIT. SM
LENGTH SURFACE PLANNED: 275' - 8 5/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8" @ 292' CONDUCTOR
ANHYDRITE T- B- 1728' ELEVATION
TD 4446 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1730 Ft. W/ 50 SX
1/2 Base Anhy. @ 920 Ft. W/ 80 SX
1/2, 1/2 Plug @ 485 Ft. W/ 40 SX
Bottom Surface @ 320 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN SM DATE 1-14-94
TYPE OF CEMENT 60/40 1/1 Plossard
STARTING TIME 6:00 (AM/PM) DATE 1-18-94
COMPLETION TIME 7:20 (AM/PM) DATE 1-18-94
CEMENT COMPANY