

1060266

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,615-60-00
100' E of S/2
NW NW, SEC. 8, T 17 S, R. 22 W/EX
4290 FSL feet N SE corner of XXXXXX section line
4520 FEL feet W SE corner of XXXXXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Higgins Well # 1

Operator: A. Scott Ritchie

County Ness

Name & Address 125 North Market, Suite 950

Well Total Depth 4398 142.94 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 247 240

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 617 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 6:00 pm Day: 11 Month: July Year: 19 84

Plugging proposal received from Bernie Meyers

(company name) Murfin (phone) 913-743-2850

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1650' with 50 sx cement

2nd plug at 825' with 50 sx cement

3rd plug at 300' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:15 pm Day: 11 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement, 2nd plug at 825' with 50 sx cement, 3rd plug at 300' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 7-30-84

Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 2261

7-11