

To: 1 070393  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-19077-00-00  
NE NW, SEC. 11, T. 17 S, R. 22 W/EX  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Ummel "AB" Well # 2

Operator: Phillips Petroleum Company  
Name &  
Address Route #3, Box 20-A  
Great Bend, KS 67530

County Ness 145.76

Well Total Depth 4485 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 17 Month: 8 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4474' Open hole Elevation 2505'

1st plug sand back to 4425' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant and Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 17 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4420' and dumped 5 sx cement on top of sand  
through bailer.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form)  
STATE CORPORATION COMMISSION  
Wichita, Kansas

**INVOLVED**

DATE 8-21-87 observe this plugging.

Signed Dan Gooder  
(TECHNICIAN)

DATE 8-21-87

INV. NO. 17911