

1 040484

10-29

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,464-00-00  
C SW NE, SEC. 35, T 16 S, R 24 W/EX  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Horchem Well # 1

Operator: John O. Farmer, Inc.

County Ness 146.90

Name & Address P.O. Box 352

Well Total Depth 4520 feet

Russell, KS 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 225.72

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 5 a.m. Day: 29 Month: 10 Year: 19 90

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1823-62'  
1st plug at 1862' with 50 sx cement, 2nd plug at 1010' with 80 sx cement,  
3rd plug at 510' with 50 sx cement, 4th plug at 240' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:15 a.m. Day: 29 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1862' with 50 sx cement,  
2nd plug at 1010' with 80 sx cement,  
3rd plug at 510' with 50 sx cement,  
4th plug at 240' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10

Remarks: Used 60/40 Pozmix 6% gel by Allied, sx cement.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-6-90

INV. NO. 29830

OCT 31 1990  
10-31-1990  
COMSERV DIVISION  
WICHITA, KANSAS

Signed Stephen J. Pfeifer (TECHNICIAN)

