

1 060576

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,821-00-00
125' W
NE SE SW, SEC. 33, T 16 S, R 24 W/EX

990 feet from S section line

3095 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Sidebottom Well # 2-33

Operator: Texas Energies, Inc.

County Ness 147.88

Name & Address P. O. Box 947

Well Total Depth 4550 (Mississippi) feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 4:00 pm Day: 25 Month: May Year: 19 85

Plugging proposal received from Tony Ernst

(company name) Wheatstate (phone) 316-672-7514

Elevation 2472 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1853-1870'

1st plug at 1860' with 50 sx cement

2nd plug at 930' with 50 sx cement

3rd plug at 340' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 pm Day: 25 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1860' with 50 sx cement, 2nd plug at 930' with 50 sx

cement, 3rd plug at 340' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

RECEIVED

STATE CORPORATION COMMISSION

MAY 31 1985

05-31-1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

(Do not) observe this plugging.

DATE 6-6-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 8356

5-25