

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02582-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 3-13S-16W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: GERSTNER Well Number: 1  
County: ELLIS Total Vertical Depth: 3400 feet

Operator License No.: 6246  
Op Name: BENNETT & SCHULTE OIL CO.  
Address: 140 WEST WICHITA AVE.  
RUSSELL, KS 67665

Production Casing Size: 4.5 feet: 3390  
Surface Casing Size: 8.625 feet: 200  
*1110<sup>50</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/27/2003 4:00 PM  
Plug Co. License No.: 31172 Plug Co. Name: L & M WELL SERVICING, INC.  
Proposal Rcvd. from: REGINALD BENNETT Company: BENNETT & SCHULTE OIL COMPA Phone: (785) 483-2721

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/27/2003 6:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1600' and 180'.  
Ran tubing to 2000'.  
Pumped 50 sxs 60/40 pozmix - 10% gel cement with 200# hulls.  
Pulled to 1000'.  
Circulated with 130 sxs cement and 300# hulls.  
Tied onto 4 1/2" - pumped 15 sxs cement.  
Max. P.S.I. 400#. S.I.P. 300#.

RECEIVED  
SEP 23 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Case Morris*  
(TECHNICIAN)

INVOICED

DATE 9.23.03  
INV. NO. 2004060533

SEP 15 2003

FRED J HAYNES

#1 GERSTNER

3-13-16W  
SW NW SW

Contr. HAYNES DRLG CO

ELLIS County

E 1977RB

Comm.

Comp. 6/30/61

IP

25 BOPD

Tops	Depth	Datum
ANH	1100	+877
TOP	2934	-957
TOR	3176	-1199
LANS	3202	-1225
TD	3400	-1423

Casing  
8" 200  
4" 3390

PERF 3240-51: ACID 2000  
SWB 50 BO/5 HR

EMMERAM

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

12401010

211