

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-15488-00-01
Spot: NWNWSW Sec/Twnshp/Rge: 3-13S-16W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: GERSTNER Well Number: 1
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 6246

Production Casing Size: 4.5 feet: 3496 EST. 200 SX CMT

Op Name: BENNETT & SCHULTE OIL CO.

Surface Casing Size: 8.625 feet: 200 EST. 150 SX CMT

Address: 140 WEST WICHITA AVE.
RUSSELL, KS 67665

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/26/2003 11:00 AM

Plug Co. License No.: 31172

Plug Co. Name: L & M WELL SERVICING, INC.

Proposal Rcvd. from: REGINALD BENNETT

Company: BENNETT & SCHULTE OIL COMM Phone: (785) 483-2721

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/26/2003 3:00 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 900' and 180' - Shot would not go down.
Ran tubing to 1500'.
Pumped 50 sxs 60/40 pozmix - 10% gel cement.
Pulled to 750'.
Pumped 130 sxs cement with 500# hulls.
Pumped 30 sxs cement with 400# hulls.
No blow - let set overnight.
Tied onto casing and pumped 20 sxs cement.
Max. P.S.I. 1000#. S.I.P. 800#.

RECEIVED
SEP 23 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Case Morris

(TECHNICIAN)

INVOICED

DATE 9-23-03

INV. NO. 2004060533

Form CP-2/3

SEP 15 2003

3-13-16W
 NW NW SW
 3-13-16W
 NW NW SW

D. A. VON FELDT #1 GERSTNER 3-13-16W NW NW SW

Contr. PABCO DRILLING COMPANY ELLIS County

E 1980 Comm. Comp. 10-6-50 IP D & A

Tops	Depth	Datum
LANS	3208	-1228
ARB	3461	-1481
T.D.	3500	-1520

Casing

DST 3461-70, 45 MIN,
REC 15' MUD

EMMERAM POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

FRED J HAYNES # 2 GERSTNER 3-13-16W NW NW SW

Contr. PABCO DRLG ELLIS County

E 1980 Comm. Comp. 4-27-62 IP 25 BOPD, 25 BW/
LANS 3235-68

Tops	Depth	Datum
LANS	3208	-1228
ARB	3461	-1480
TD	3500	-1520

Casing

DST 3461-70/45", 15' M
WAS D & A, D A VON FELDT,
10-6-50: NEW INFO: CO 3500
SET 4 1/2" 3496: PERF 3365-68
3235-52: ACID 2000

EMMERAM POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS