

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25077-00-00  
Spot: E2 Sec/Twnshp/Rge: 3-13S-16W  
2710 feet from S Section Line, 1150 feet from E Section Line  
Lease/Unit Name: MILLER A Well Number: 1  
County: ELLIS Total Vertical Depth: 3525 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 221  
Production: Size feet:  
Liner: Size feet:

\$114.56

Well Type: DH UIC Docket No: Date/Time to Plug: 02/07/2001 3:00 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 170 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 02/07/2001 5:45 PM

WitnessType: Plugging Operations Were Not Witnessed  
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1165' w/25 sxs. Anhydrite 1135' - 1175'.  
2nd. Plug at 625' w/80 sxs. Dakota 307' - 607'.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

INVOICED  
DATE 03-06-2001  
INV. NO. 2001010217

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 2001

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: SWIFT CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)