

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25165-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 32-11S-17W  
2970 feet from S Section Line, 4215 feet from E Section Line  
Lease/Unit Name: C. M. HADLEY Well Number: 7  
County: ELLIS Total Vertical Depth: 3618 feet

Operator License No.: 6509

Conductor Pipe: Size feet: \$117.59

Op Name: CLARK, JIM D. DBA CLA-MAR OIL, COM Surface Casing: Size 8.625 feet: 208

Address: PO BOX 1197  
HAYS, KS 67601

Production: Size feet:

Liner: Size feet:

Well Type: DH

UIC Docket No:

Date/Time to Plug: 11/11/2002 11:00 PM

Plug Co. License No.: 9431

Plug Co. Name: VONFELDT DRILLING, INC

Proposal Rcvd. from: DOUG BUDIG

Company: VONFELDT DRILLING, INC

Phone: (785) 483-6446

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 11/11/2002 11:50 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3535' w/25 sxs. Anhydrite 1278' - 1340'.  
2nd. Plug at 1325' w/25 sxs. Surface pipe set to 208'.  
3rd. Plug at 725' w/100 sxs.  
4th. Plug at 265' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
NOV 18 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 11-19-02

INV. NO. 2003060831

NOV 14 2002