

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25168-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 32-11S-17W
390 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: KESSLER Well Number: 5
County: ELLIS Total Vertical Depth: 3668 feet

Operator License No.: 32754
Op Name: ELYSIUM ENERGY, L.L.C.
Address: 1625 BROADWAY, SU 2000
DENVER, CO 80202

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 225
Production: Size feet:
Liner: Size feet:

\$119.21

Well Type: DH UIC Docket No: Date/Time to Plug: 11/09/2002 9:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Plugging Space all plugs with heavy drilling mud through drill pipe.
Method: Ar buckle not found.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 11/09/2002 12:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1350' w/50 sxs. Anhydrite 1329' - 1361'.
2nd. Plug at 800' w/100 sxs. Dakota 482' - 782'.
3rd. Plug at 275' w/40 sxs. Surface pipe set to 225'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
NOV 18 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 11-19-02

INV. NO. 2003060832

NOV 14 2002