

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19272-00-01
Spot: NESESWSW Sec/Twnshp/Rge: 3-32S-12E
649 feet from S Section Line, 4082 feet from E Section Line
Lease Name: LONGTON STORAGE Well #: 21A
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2011 12:00 AM
Plug Co. License No.: 34453 Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION
Proposal Rcvd. from: ANDREW NEGLEY Company: _____ Phone: (620) 431-9500

Proposed Plugging Method: Pull any remaining downhole that has not been cemented. Run pipe to TD. Circulate cement to surface. Trip pipe out. Fill up backside at surface if necessary. Remediate locations by removing any surface equipment, fill in pits, cutting casing off 3' below surface and backfill the hole.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 09/14/2011 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated casing at 350' and 150'. Ran 1" to 620' and circulated cement to surface. Tried to pull 1" and was hung in hole. Unscrewed from 1" and pulled 3 joints out of well. Hooked onto casing and squeezed well and shut in at 400 psi. A total of 125 sacks of cement were used to plug this well.

Perfs:

RECEIVED
APR 19 2012
KCC WICHITA

RECEIVED

APR 16 2012 DAS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)