

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19271-00-01
Spot: NESESWSE Sec/Twnshp/Rge: 4-32S-12E
478 feet from S Section Line, 1359 feet from E Section Line
Lease Name: LONGTON STORAGE Well #: 12
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33343

Op Name: POSTROCK MIDCONTINENT PRODUC

Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

Well Type: GWI

UIC Docket No:

Date/Time to Plug: 04/08/2010 10:00 AM

Plug Co. License No.: 34453

Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION

Proposal Revd. from: ERNIE GONZALEZ

Company:

Phone: (405) 600-7704

Proposed Plugging Method: Clean well bore out, perforate well were needed and cement bottom to top inside and outside of casing.

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed 04/08/2010 11:30 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Operator had already set cast iron bridge plug at 522' and perforated well at 440'-444', 450'-454'. Both of these perforations were 1 shot per foot. Operator ran 1" to cast iron bridge plug and circulated cement to surface. Pulled 1" and hooked onto casing. Operator than pumped cement and couldn't get well to pressure up. Let well set for thirty minutes and pumped more cement to try and squeeze cement up backside. Operators pump truck than broke down so no pressure was established on casing. A total of 130 sacks of cement were used to plug this well.

RECEIVED

APR 16 2012 DAS

KCC Chanute Dist. #3

RECEIVED

APR 19 2012


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)