

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19284-00-01
Spot: SWNWNWNE Sec/Twnshp/Rge: 9-32S-12E
4656 feet from S Section Line, 2620 feet from E Section Line
Lease Name: LONGTON STORAGE Well #: 5
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33343

Op Name: POSTROCK MIDCONTINENT PRODUC

Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 10/03/2011 12:00 AM

Plug Co. License No.: 34453

Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION

Proposal Rcvd. from: ANDREW NEGLEY

Company:

Phone: (620) 431-9500

Proposed Plugging Method: Pull any remaining downhole that has not been cemented. Run pipe to TD. Circulate cement to surface. Trip pipe out. Fill up backside at surface if necessary. Remediate location by removing any surface equipment, fill in pits, cutting casing off 3' below surface and backfill the hole.

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed 10/03/2011 2:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Perforated casing at 350' and 150'. Ran 1/2" to 680' and pumped 20 sacks of cement. Pulled 350' of the 1/2" out and circulated cement to surface. Pulled 1/2" and topped well off. A total of 50 sacks of cement were used to plug this well.

RECEIVED

APR 16 2012 DAS

KCC Chanute Dist. #3

RECEIVED

APR 19 2012


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Form CP-2/3

5/10/12