

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19282-00-01
Spot: NWNESENE Sec/Twnshp/Rge: 9-32S-12E
3926 feet from S Section Line, 392 feet from E Section Line
Lease Name: LONGTON STORAGE Well #: 2
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/21/2011 12:00 AM
Plug Co. License No.: 34453 Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION
Proposal Rcvd. from: ANDREW NEGLEY Company: _____ Phone: (620) 431-9500

Proposed Pull any remaining downhole that has not been cemented. Run pipe to TD. Circulate cement to surface. Trip pipe out. Fill
Plugging up backside to surface if necessary. Redmediate location by removing any surface equipment, fill in pits, cutting casing off
Method: 3' below surface and backfill the hole

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 09/21/2011 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Perforated casing at 350' and 150'. Ran 1" to 690' and circulated cement to surface. Pulled 1" out of well. Hooked onto casing and squeezed cement down well until casing pressured up to 800 psi. A total of 115 sacks of cement were used to plug this well.

RECEIVED
APR 16 2012 DAS
KCC Chanute Dist. #3

RECEIVED
APR 19 2012
KCC WICHITA

Remarks:
Plugged through: TBG

District: 03 Signed Duane A Sims
(TECHNICIAN)

Form CP-2/3
5/07/12