

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19669-00-01
Spot: SWNESE Sec/Twnshp/Rge: 9-32S-12E
2003 feet from S Section Line, 641 feet from E Section Line
Lease Name: LONGTON PHANTOM Well #: 2
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/05/2011 12:00 AM
Plug Co. License No.: 34453 Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION
Proposal Rcvd. from: ANDREW NEGLEY Company: _____ Phone: (620) 431-9500

Proposed Plugging Method: Pull any remaining downhole that has not been cemented. Run pipe to TD. Circulate cement to surface. Trip pipe out. Fill up backside at surface if necessary. Remediate location by removing any surface equipment, fill in pits, cutting casing off 3' below surface and backfill the hole.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 10/05/2011 2:00 PM KCC Agent: LARRY MARCHANT

Actual Plugging Report:

Perfs:

Perforated casing at 350' and 130'. Tried to pull 1 1/2" and broke it off. Pulled 350' of 1 1/2". Ran 2" to top of 1 1/2" and hung in hole. Ran 1/2" to 560' inside 2" and 1 1/2". Pumped 2 sacks of gel. Pumped 20 sacks of cement and pulled 1/2". Hooked back onto 2" and circulated cement to surface. Pulled 2" and topped well off. A total of 70 sacks of cement were used to plug this well.

RECEIVED
APR 16 2012
KCC Chanute Dist. #3

DAS

RECEIVED
APR 19 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Duane A Sims
(TECHNICIAN)

5/07/12