

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22150-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 10-28S-9W
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: WEGMAN Well #: 1-10
County: KINGMAN Total Vertical Depth: 4456 feet

Operator License No.: 31160
Op Name: PHILLIPS EXPLORATION COMPANY L.
Address: 1601 SAGEBRUSH
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		200 sx
TI	2.375	4075		
PROD	5.5	4451	2450	175 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/23/2011 12:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TOM DIXSON Company: D S & W WELL SERVICING Phone: (316) 636-2256

Proposed Plugging Method: AS PER KCC ORDERS.

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL
Date/Time Plugging Completed: 08/24/2011 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3950' - CAPPED WITH 5 SX CEMENT. CUT CASING OFF @ 2450' -
PULLED CASING TO 1340' SPOTTED 35 SX CEMENT - TAGGED CEMENT @ 1300'
PULLED CASING TO 872' - SPOTTED 35 SX CEMENT - PULLED CASING TO - 256'
CIRCULATED TO SURFACE WITH 100 SX

Perfs:

Top	Bot	Thru	Comments
4030	4032		

RECEIVED
APR 19 2012
KCC WICHITA

Remarks: ALLIED OUT OF MEDICINE LODGE - 60/40 4% POZ MIX WITH 3% CC. TICKET #40770.

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

Form CP-2/3

5/07/12

JK